USACE GREAT LAKES NAVIGATION SYTEM UPDATES

GL Navigation Team

Nick Zager – Great Lakes Nav System Lead & Operations Chief – Detroit

Paul Mazzeno – Operations Division Chief – Chicago

Dave Swiatek – Operations and Technical Support Chief – Buffalo

AGLPA – 2024 Annual Conference Chicago, IL 9 August 2023










AGENDA

- Dredging Funding Overview
- Dredging Backlog Quantities
- Great Lakes Navigation Structures
- Great Lakes Navigation Focus Areas
- Project Highlights
 - Detroit
 - Buffalo
 - Chicago
- Great Lakes Navigation Website Update



GL NAVIGATION FUNDING HISTORY





FY24 GREAT LAKES NAVIGATION FUNDING

FY24 President's Budget - \$274.18M

\$67.23M Dredging (3.05M CY) \$97.99M Soo Locks Asset Renewal/Maintenance \$26.9M Lock Operations

FY24 Work Plan - \$81.52M

\$13.97M Dredging (0.28M CY) \$37.88M Structure Design, Maintenance, and Repairs \$29.84M Soo Locks Asset Renewal/Maintenance

FY24 Congressionally Directed Spending – \$12.58M

\$3.24M Dredging (0.24M CY) \$8.84M Structure Design, Maintenance, and Repairs \$0.50M Clinton River Dredge Material Management Plan

FY24 Bipartisan Infrastructure Law - \$13.4M

\$0.2M Dredging – Big Suamico \$13.2M Structure Design, Maintenance, and Repairs

- \$8.22M Lexington Breakwater Repair
- \$5.0M Black Rock Channel –
 Construction of Bird Island Pier



FY25 GREAT LAKES NAVIGATION FUNDING PRESIDENT'S BUDGET

Great Lakes Navigation Operation & Maintenance \$189.2M

Key O&M Items

\$70.77M in Dredging (24 projects; 3.1M cy)

\$16.48M in Dredged Material Management

\$15.8M Floating Plant Fleet Repair

\$18.6M in Soo Locks Asset Renewal/Maintenance

\$7.0M in Black Rock Lock Asset Renewal


\$28.22M in Lock Operation and Maintenance

\$4.5M in Navigation Structure Maintenance/Repair

\$1.6M in Sediment Sampling for Dredging



FY25 DREDGING FUNDING AND DREDGING REQUIREMENTS



FY25




FY07

FY09

FY11

FY13




FY15

FY17

FY19

FY21





GREAT LAKES NAVIGATION STRUCTURES


- 104+ miles of navigation structures on the Great Lakes
- Structures include piers, jetties, revetments, and breakwaters
- Most were built between 1860 and 1940
- Jetties and piers were constructed perpendicular to shore to keep the channel open for navigation
- Off-shore breakwaters were constructed to allow safe navigation entry to harbors and channels
- 60% of GL coastal structures were built before WWI
- Over 90% of all coastal structures exceed 60 years of age
- Over 30% of structures have timber crib core sections; past low water levels have accelerated deterioration of the wood
- Over 40% of structure segments are rated C - F; backlog funding need is estimated at \$320M





NAVIGATION STRUCTURES FUNDING

■ Navigation Structures Expenditures (Adjusted to FY07 levels for value prior to FY07)






GREAT LAKES NAVIGATION SYSTEM FOCUS AREAS

- **Dredging and Dredged Material Management** DMMPs and CDF capacity issues
 - Leverage opportunities for Beneficial Use of Dredged Material
 - Chief of Engineers goal 70% Beneficial Use by 2030
- Navigation Structures continue to prioritize needs of repairs to navigation structures on the Great Lakes that will ensure safe navigation is maintained
- **Asset Renewal** ensure efficient and reliable navigation through investments in lock structures in the system, leveraging new technologies and minimize risk of unscheduled outages
- Stakeholder Engagement encourage two-way coordination and communication; obtaining stakeholder input on critical system needs and consequences is an important part of helping the Corps make the best investment decisions



USACE Great Lakes Navigation Webpage:

https://www.lrd.usace.army.mil/Water-Information/Navigation/Great-Lakes/Great-Lakes-Navigation-Dredging/



SAULT STE. MARIE MAINTENANCE – 3D PRINTING

- Cracks discovered in existing Poe Lock ship arrestor lever arm casting during ongoing rehabilitation contract in February 2023. Plan was to reuse existing lever arm. Performed emergency crack repair & put back in service, \$71k.
- New lever arm design optimized for ease of future O&M.
- Supply Contract for 3D Printed Part in September 2023, 12 weeks (prep, build strategy, 3D printing, shipping, joining, stress relief, x-ray testing), \$215k
- GOV supplied to Prime Contractor (Dec '23); machined, painted, & shipped in 4 weeks, \$92k. Installed March 2024.

Total Fab. Time = 16 weeks vs. Traditional Casting = 52 weeks

Existing Casting Repair



New Lever Arm Installation








3D Build by Lincoln Electric Additive Solutions

- Print Time 2 weeks smaller part (2000lb), 4 weeks larger part (4000lb), simultaneous build = 4 weeks.
- Material High Strength Low Alloy Metal










DULUTH DREDGE MATERIAL MANAGEMENT






Recent Success & Ongoing Projects

- Maintenance Dredging (FY21, FY22, FY23 & FY24)
 - FY24 M/D with Nearshore Placement on WI Point
- Dredged Material Management and Beneficial Use (FY22 & FY24)
 - Funds to remove and beneficially reuse material from Erie Pier CDF and monitor performance of the material
- Sediment Sampling and Analysis (FY23)
 - Harbor-wide characterization will support identification of future beneficial use opportunities


Future Work & Challenges

- **Continued Annual Maintenance Dredging**
 - · Annual maintenance dredging need exceeds available CDF capacity
 - Currently no implementable beneficial use projects ready to support future dredging projects
- Erie Pier Confined Disposal Facility
 - Continued fill management necessary for placement capacity
 - Over 200,000CY of fine material stockpiled, challenge in identifying shovel-ready projects to receive material
- Nearshore Placement
 - Environmental and cultural resource coordination adds cost and time to project





DREDGED MATERIAL MANAGEMENT







Recent Success & Ongoing Projects


- Burns Waterway -- Maintenance dredging 40K CY (FY24)
- Green Bay -- Sediment sampling/analysis (FY24);
 Maintenance dredging 180K CY (FY24)
- Indiana -- Dredged Material Disposal Facility (DMDF) expansion complete; Maintenance dredging to address 78K CY backlog (FY24)
- Milwaukee -- Maintenance dredging 56K CY (FY23)

Challenges & Future Work

- Burns Waterway -- Maintenance dredging (FY26)
- Calumet -- Planned DMDF vertical expansion project and future dredging on hold pending court case and State of Illinois permitting
- Indiana -- Maintenance dredging (FY26)
- Green Bay -- Maintenance dredging (FY25/26/27);
 Operation & Maintenance (O&M) of DMDF (FY25)
- Milwaukee -- Sediment sampling/analysis (FY25);
 DMMP(FY26)



MAVIGATION STRUCTURE REPAIR





Recent Success & Ongoing Projects

- Milwaukee Harbor -- South detached breakwater (USACE Fleet, FY24)
- Calumet Harbor -- North breakwater (USACE Fleet, FY24)
- Chicago Harbor -- Southerly extension breakwater grouting (FY24); Shore arm extension breakwater stone placement (FY24)


Challenges & Future Work

- Calumet -- North breakwater (USACE Fleet, FY25/26/27)
- Chicago -- Southerly extension breakwater stone placement (USACE Fleet, FY25)
- Milwaukee Harbor -- South detached breakwater (USACE Fleet, FY25)
- Fluctuating stone prices




INTERCONNECTIVITY BETWEEN GREAT LAKES AND ILLINOIS WATERWAY

INDIANA HARBOR








HAH


DREDGED MATERIAL MANAGEMENT

Maintenance Dredging Historic Funding











Buffalo



Recent Success

- Conneaut Harbor Sediment Processing Facility completed in 2024
 - Dredging completed in 2024 for first time since 2019
 - 2024 dredging will place ~80,000 CY of material into facility
- Buffalo Outer Harbor Section 204 Beneficial Use Project
 - Restoration of coastal wetland habitat at an abandoned slip using sediment dredged from the Buffalo River and Harbor.
 - Total capacity of 285,000 CY
 - 2024 dredging will place ~80,000 CY


Future Challenges

- Near term (1-5 years)
 - Sandusky FY24 dredging cancelled due to lack of placement site. Work in the harbor on-hold until new placement site is available
 - Rising dredging and placement costs
 - Availability of contractors
- Long term (5, 10, 20 year)
 - · Establishing Section 217 Agreements to set tipping fees
 - Completing DMMPs to ensure 20-year capacity
 - Continuing to identify and implement Beneficial Use (BU) projects to support Chief of Engineers goal of 70% by 2030

HAH .

CONTRACTED STRUCTURE REPAIR







Successes

- Completed (10) Cleveland East Breakwater West End (2021); Cleveland West Breakwater (2023); Great Sodus East Breakwater East End (2021); Vermilion East Pier North End (2021) and West Pier North End (2023); Little Sodus West Pier (2022); Rochester East Pier (2023) Buffalo South Breakwater (2022) and North Breakwater North End (2024) and South End (2024)
- Ongoing (5) Cleveland West Pier (2024); Erie North Pier (2024); Oswego West Arrowhead Phase 3 (2024) & Phase 4 (2025); Vermilion West Pier South End (2024/25)
- Upcoming (10) BRL Bird Island Pier Phase 1 & 2 (2025/26); Dunkirk Outer Breakwater East Side and West End (2025/26); Lorain West Breakwater (2025/26); Great Sodus East Breakwater (2025/26); Huron West Pier (2025/26); Oswego Outer West Breakwater (2025/26); Vermilion East Pier South End (2025); Barcelona West Breakwater (2026)

Challenges

- Large workload and limited availability of contractors has stressed existing contractor capacity and material availability resulting in:
 - Higher costs
 - Longer construction windows
 - Reduced repair lengths



GREAT LAKES NAVIGATION TEAM WEBSITE & NEXT MEETING

- NEW website, NEW Look, and NEW GIS portals are here
- https://www.lrd.usace.army.mil/Wa ter-Information/Navigation/Great-Lakes/Great-Lakes-Navigation-Dredging/
- For support or questions on the new website please reach out to the Great Lakes Navigation Team at GLNavigation@usace.army.mil
- Nov 14: Annual meeting at the Port of Detroit

